

CITY OF MARTINSVILLE
FRANKLIN STREET CURB & GUTTER INSTALLATION
ADDENDUM No. 1
AUGUST 19, 2016

The following items are presented as additional clarifications and statements:

1. A copy of the pre-bid minutes is included for reference.
2. The completion date has been moved to November 11, 2016.
3. High Early concrete mix is to be used on driveway entrances to allow for their use as soon as possible by the residents.

End of Addendum No. 1

CITY OF MARTINSVILLE
FRANKLIN STREET CURB & GUTTER INSTALLATION
PRE-BID MEETING
August 18, 2016

1. Bid Date: Thursday August 25, 2016 at 2:00 p.m. at Fishel Street Warehouse.
2. Bid Bond: A bid bond equal to 5% of the contractor's bid is required.
3. Performance Bond: A bond equal to 100% of the contractor's bid is required, if successful.
4. All construction is scheduled to be completed by ~~October 14, 2016~~ **November 11, 2016**.
5. Traffic control will be provided by the City of Martinsville.
6. Work includes: Installation of 2135 LF of standard CG-6 and 10 driveway entrances. **High early concrete mix design is to be used on the driveway entrances.**
7. Chris Morris, City Engineer/ Assistant Public Works Director, is the designated project manager for the project 403-5159.
8. Inspection will be handled by the City Engineering Department, Weldon Reynolds and David Collie 403-5160.
9. Questions?
 - **The City will place stone for the curb & Gutter and driveway bases.**
 - **The City will saw-cut the pavement to allow for 8"-12" of space from the face of gutter.**